



JAMINI ROY COLLEGE

(NAAC Accredited - B)

P.O. - BELIATORE, DIST.- BANKURA (W.B.), PIN - 722203

TEL. No. : 03241-259261, Email ID - jamini.roy.college.261@gmail.com

Ref. No.

29.09.2023

Date.....


From :

Principal / Teacher Incharge
Jamini Roy College
Beliatore, Bankura

Tender Notice No- 29

এতদ্বারা যামিনী রায় কলেজের **যামিনী রায়ের মূর্তির** স্থান পরিবর্তন করার জন্য, সিল করা দরপত্র আহবান করা হচ্ছে। দরপত্রটি কলেজ অফিসে জমা দেওয়ার শেষ তারিখ (**17.10.23**) বৈকাল **1:00** টার মধ্যে। দরপত্রে অতি অবশ্যই কন্টাক্ট নাম্বার থাকতে হবে। কাজের ব্যাপারে বিশদ জানার জন্য যামিনী রায় কলেজের ওয়েবসাইট অনুসরণ করার জন্য জানানো হচ্ছে। দরপত্র খোলার দিন **17.10.23** দুপুর **2:30** এর মধ্যে।

দরপত্র খোলার সময় বিডারদের উপস্থিত থাকা বাধ্যতামূলক নয়।


Principal
Dr. Pradip Kumar Banerjee
Principal
Jamini Roy College
Beliatore, Bankura (W.B.)

**ESTIMATE OF EXTRA WORK AT MUKTAMANCHO OF JAMONI ROY
COLLEGE BELIATORE, BANKURA**

SL. NO.	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (₹)	AMOUNT (₹)
1	<u>Page-1, Item No.-2, P.W.D. Schedule.</u> Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm.	1.87	%M ³	11927.00	222.91
2	<u>Page-2, Item No.-4, P.W.D. Schedule.</u> Filling in foundation or plinth by silver sand in layers not exceeding 150 mm. as directed and consolidating same by thorough saturation with water ramming complete, including the cost of supply of sand. (Payment to be made on measurement of finished quantity)	0.31	%M ³	37521.00	116.87
3	<u>Page-14, Item No.-1, P.W.D. Schedule.</u> Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	3.07	M ²	293.00	898.28
4	<u>Page-11, Item No.-5, P.W.D. Schedule.</u> Ordinary Cement Concrete M - 15 (mix 4:2:1) with graded stone chips (20 mm. down) excluding shuttering and reinforcement, if any, in ground floor, as per IS 456-2000. a) Pakur / Chandil Variety.	0.21	M ³	3525.00	724.67
6	<u>Page-18, Item No.-29, P.W.D. Schedule.</u> Brick work with 1st class bricks in cement mortar (6:1) (a) In foundation and plinth (b) In superstructure, ground floor	0.99 3.11	M ³ M ³	4861.00 5051.00	4792.22 15704.52
14	<u>Page-189, Item No.-1, P.W.D. Schedule.</u> Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints or roughening of concrete surface, including throating, nosing and drip course where necessary (ground floor) (c) With (6:1) cement mortar, 15mm. thick.	12.26	M ²	133.00	1631.01
15	<u>Page-62, Item No.-31, P.W.D. Schedule.</u> Supplying, fitting & fixing granite tiles 10mm to 12mm. thick in columns, wall, fascia etc. with 15 thick [avg] cement mortar (1:2) including making suitable arrangements to hold the stones properly by brass / copper hooks including pointing in cement mortar (1:2) (1 white cement : 2 marble dust) with admixture of pigment matching the stone shades all complete as per direction of the Engineer-in-charge including cost of all materials, labours, scaffolding, staging, curing and roughening of concrete surface complete. <small>Using cement slurry at back side of tiles @ 4.4 kg/sq.m. & white</small>				


 Dr. Pradip K. Banerjee
 Principal
 Jamini Roy College
 Beliapore, Bankura (W.B.)


 Indrajit Ghosh (D.C.E.)
 Building Planner & Estimator
 Beliapore, Bankura

18	(i) area of each slab/tile upto 0.30 SqM <u>Page-196 Item No.-8, P.W.D. Schedule.</u> Applying Exterior grade Acrylic primer of approved quality and brand on plaster or concrete surface old and new surface receive Texture(mat finish) or smoth finish acrylic exterior emulsion paint including cleaning and preparing the surface throughly, complete. / Acrylic emulsion paint and preparing the surface throughly, complete as per manufacture specification of the E.I.C. In ground floor. a) One coats	10.22	M ²	1743.00	17812.30
19	<u>Page-163, Item No.-9, P.W.D. Schedule.</u> Applying Arcylic Emalsion paint of approved make and brand on walls and celling including putty (to be done under specific instruction of superintending engg.) : ii) Luxury quality (Two coats)	12.26	M ²	31.40	385.06
20	<u>Page-197, Item No.-17, P.W.D. Schedule.</u> Protective and decorative Acrylic Exterior emulsion Paint of approved quality as per manufacturer's specification and as per direction of Engineer -in Charge to be applied over acrylic Primer as required. The rates includes the cost of materials, labour, scaffolding and all others incidental charges but excluding and all others incidental charges but excluding the cost of primer. b) Premium 100% Acrylic Emulsion		M ²	76.00	
21	Supplying & laying as per IRC-SP:063-2004 paver unit of any shade of approved quality as per relevant IS code, laid in pattern as directed in pavement, footpath, driveway (paver block only), etc including necessary underlay complete in all respect with all labour and material. [Border concrete if necessary to be paid separately]. Note: Sub-grade CBR should not be less than 5. a) 25 mm thick Tiles as per IS: 1237-2012 for footpath,ramp,staircase of public building(over 25 mm thick	12.26	M ²	84.00	1030.11
		24.27	M ²	863.00	20945.01
				TOTAL	64262.96
				Sub-total Cost:-	64262.96
				Contingency Charge @ 3%	1927.89
				GRAND TOTAL:-	66190.85
				SAY-	66191.00

Rupees sixty six thousand one hundred ninety nine only

Dr. Pradip Kr. Banerjee
Principal
Jamini Roy College
Beliatore, Bankura (W.B.)

Indrajit Ghosh
20/8/23
Indrajit Ghosh (D.C.E.)
Building Planer & Estimator
Beliatore, Bankura