



# JAMINI ROY COLLEGE

P.O.-BELIATORE, DIST.-BANKURA (W.B.), PIN-722203

TEL. No. : 03241-259261, Email ID : jamini.roy.college.261@gmail.com

Ref. No. \_\_\_\_\_

Date 7/8/24

From :

Principal / Teacher-in-charge  
Jamini Roy College  
Beliatore, Bankura

## দরপত্রের বিজ্ঞপ্তি নম্বর - ৩৬

এতদ্বারা যামিনী রায় কলেজের রাস্তার ১০৩.১২৫ ঘনমিটার মোরামমাটির জন্য সীল করা দরপত্র আহ্বান করা হচ্ছে। দরপত্র কলেজ অফিসে জমা দেওয়ার তারিখ ২১.০৬.২০২৪ এর মধ্যে। দরপত্রে অবশ্যই Contact No. থাকতে হবে।

  
Principal  
Jamini Roy College  
Beliatore, Bankura (W.B.)


**ESTIMATE FOR EARTH FILLING IN BETWEEN WEST SIDE OF GARDEN & NEW BUILDING AT BELIATORE JAMINI ROY COLLEGE AT BELIATORE IN THE DISTRICT OF BANKURA.**

Sl. No.	Description of Items	No.	Length	Breath	Height	Quantity	Unit	Rate	Amount
			Meter	Meter	Meter			₹	₹
1	<b>BW: I-A-3-c(ii),P-1</b>								
	Earth work in filling in foundation trenches, plinth, pits, etc. with good soil in layer not exceeding 150 mm including watering, ramming, etc. layer by layer complete (Payment to be made on basis of measurement of finished quantity of work.) (iii) With carried earth arranged by the contractor within a radius exceeding 3 km. but not exceeding 5 km. including the cost of carried earth.								
	For pathway	1	35.000	2.500	0.750	65.625			
		1	14.000	2.500	0.750	26.250			
		1	10.000	1.500	0.750	11.250			
	Total					103.125			
						1.03125	% CuM.	39901.00	41147.91
	Total							₹	41147.91
	Add 9% for CGST							₹	3703.31
	Add 9% for SGST								3703.31
	Gross Total							₹	48554.53
	Add 1% for Labour Cess							₹	485.55
	Net Total							₹	49040.08
	Say							₹	49,040.00

(Rupees Forty Nine Thousand Forty Only)

Payment will be made for all items after finishing as per EIC as per Govt. norms.

  
**Principal**  
**Jamini Roy College**  
 Beliatore, Bankura (W.B.)

  
**ARINDAM KARMAKAR**  
**DMC/BPD/LBS-II/213**  
**Barjora, Bankura**  
 Arindam Karmakar (D.C.E.)  
 Barjora, Bankura  
 Prepared By


**ESTIMATE FOR EARTH FILLING IN BETWEEN WEST SIDE OF GARDEN & NEW BUILDING AT BELIATORE JAMINI ROY COLLEGE AT BELIATORE IN THE DISTRICT OF BANKURA.**

Sl. No.	Description of Items	No.	Length	Breath	Height	Quantity	Unit	Rate	Amount
			Meter	Meter	Meter			c	c
1	<b>BW: I-A-5,P-2</b>								
	Earth work in filling in compound, tank, low land, ditches etc. with good earth, in layers not exceeding 150 mm. including breaking clods and consolidating the same by ramming and dressing complete. (Payment will be made on profile measurement before and after the work) (a) With earth obtained by fresh excavation upto 1800 mm. depth (including the cost of excavation from land arranged by the Deptt. within a lead of 100 m.)								
	For pathway	1	35.000	2.500	0.750	65.625			
		1	14.000	2.500	0.750	26.250			
		1	10.000	1.500	0.750	11.250			
	Total					103.125			
						1.03125	% CuM.	17218.00	17756.06
	Total							c	17756.06
	Add 9% for CGST							c	1598.05
	Add 9% for SGST								1598.05
	Gross Total							c	20952.15
	Add 1% for Labour Cess							c	209.52
	Net Total							c	<b>21161.67</b>
	Say							c	<b>21,162.00</b>

(Rupees Twenty One Thousand One Hundred Sixty Two Only)

Payment will be made for all items after finishing as per EIC as per Govt. norms.

  
**Principal**  
**Jamini Roy College**  
**Beliatore, Bankura (W.B.)**

  
**ARINDAM KARMAKAR**  
**DMC/BPD/LBS-II/213**  
**Barjora, Bankura**  
 Arindam Karmakar (D.C.E.)  
 Barjora, Bankura  
 Prepared By